APARTMENT COMPACTOR DEALER DELIVERY CHECK SHEET


TO BE CHECKED BY DEALER


CUSTOMER	DATE	
ADDRESS		
DEALER		
ADDRESS		
	SERIAL NUMBER	
POWER UNIT MODEL	SERIAL NUMBER	
DEALER CHECK:		
1Check that power unit reservoir is full o	f oil.	
2Check that compactor is installed, leveled, and anchored properly.		
3Check that hydraulic hoses from the po	wer pack are connected correctly.	
4Check that all decals are in place and standards been met.	I legible. Have requirements of current ANSI Z245	
5Check compactor operation, start and s	stop.	
6Check if ram area has been lubricated.		
DELIVERED BY	DATE	
1Owner's manual has been provided.		
2Warranty card is filled out and mailed.		
3Reviewed the safety warnings and cau	tions listed in this manual.	
4Reviewed the maintenance instructions	and cautions as listed in this manual.	
REVIEWED BY	DATE	

Rev.8/05

Table of Contents

WARRANTY		INSTRUCTIONS FOR CONVERTING 3-PHASE	
DEALER DELIVERY CHECK SHEET	1	POWER UNIT VOLTAGE	013
TABLE OF CONTENTS	3		PHASE
SPECIFICATIONS	4-5	POWER UNIT VOLTAGE	014
SAFETY DECALS	6	PARTS SECTION	
OPERATING INSTRUCTIONS		APARTMENT COMPACTOR ASSEMBLY	P
INSTALLATION INSTRUCTIONS	01	SIDE LATCH ASSEMBLY	PS
Installation Site	01	POWER UNIT ASSEMBLY (Sequence)	P4-P5
Safety Decal Requirements	02	3-PHASE POWER PANEL (Sequence)	P6-P7
Electrical Installation	02	SINGLE PHASE POWER PANEL (Sequence)	P8-P9
Electrical Requirements	О3	` ' '	
START-UP AND TESTING INSTRUCTIONS	O3	3HP HYDRAULIC SCHEMATIC (Sequence)	P10
OPERATING INSTRUCTIONS	03	1 HP HYDRAULIC SCHEMATIC (Sequence)	P11
Employer Responsibility for Compactor	O5	110V 1-PHASE ELECTRIC SCHEM. (Sequence)	P12
Operating Instructions for Standard Compactors	O5	220V 1-PHASE ELECTRIC SCHEM. (Sequence)	P13
Optional Features	06	3HP 3-PHASE ELECTRIC SCHEMATIC (Sequence	e) P15
MAINTENANCE INSTRUCTIONS	06	3 HP POWER UNIT ASSEMBLY (Electric)	16-P17
Work Area Around Compactors	06	1HP POWER UNIT ASSEMBLY (Electric)	18-P19
HYDRAULIC SAFETY: READ CAREFULLY	07	3 HP POWER PANEL ASSEMBLY (Electric) P2	20-P21
Avoid Heating Near Pressurized Lines	07	, ,	22-P23
Warnings pertaining to common abuses of hoses	07	,	
Preventive Maintenance	07	1 & 3 HP HYDRAULIC SCHEMATIC (Electric)	P24
Initial Check	08	3HP, 3-PHASE ELECTRIC SCHEMATIC (Electric)	P2
Monthly Check	08	1HP, 3PHASE ELECTRIC SCHEMATIC (Electric)	P26
3-Month Check	08	3HP, 3PHASE SCHEMATIC (Electric Eye, Alarm)	P27
Filter Maintenance	07	1HP, 1-PHASE SCHEMATIC (Electric Eye, Alarm)	P28
Annual Compactor Inspection	07	HYD. CONTROL VALVE ASSEMBLY (Sequence)	P29
Sequence Valve, Relief Valve, Pressure Switch Adj.	08	PRINCE HYDRAULIC CYLINDER ASSEMBLY	P30
Pressure Setting and Adjusting Procedures	08		
Electric Control Valve Pressure Setting	09	OVERHEAD CHUTE HOPPER W/ ACCESS DOOR	
GENERAL MAINTENANCE TIPS	010	FULL ENCLOSED HOPPER	P32
TROUBLE-SHOOTING	011	DECALS	P33
ELECTRIC MOTOR TROUBLE-SHOOTING	012		







KP03 SPECIFICATIONS

ELECTRICAL EQUIPMENT

Motor 3HP 208 / 230 / 460 3-Phase 60 Cycle

Motor 1HP 110 / 220 1-Phase 60 Cycle

Control voltage 115 VAC

All circuits fused

Key operated Start / Stop / Reverse

HYDRAULIC EQUIPMENT

Pump 5 GPM 3HP/3 GPM 1HP

Normal Pressure 1,850 PSI

Maximum Pressure 2,100 PSI

Hydraulic Cylinder 2 Diagonal 2.5" x 20" Stroke

PERFORMANCE SPECIFICATIONS

Cycle Time (In Seconds) 18 3HP / 29 1HP

Ram penetration 6"

Normal Packing Force 15,450#

Maximum Packing Force 17,540#

Normal Ram Face Pressure 31.3 PSI

Max. Ram Face Pressure 35.4 PSI

SPECIFICATIONS

Charge Chamber Capacity

Mfg. rating $1/3 \text{ yd}^3$

Clear top opening 22.5" L x 28" W

Ram face 16.5" x 30" x .38"

Loading Height 42"

Weight (Includes Power Unit) . . . 1,530 lbs.

M9103-24

SAFETY DECALS

Be sure to read all safety decals carefully.

BEFORE OPENING DOOR:

TURN CONTROL PANEL KEY SWITCH TO OFF POSITION, REMOVE KEY, AND **BLOCK OFF TRASH CHUTE.**

THIS COMPACTOR **STARTS AUTOMATICALLY!**

CAUTION

DO NOT REMOVE ACCESS COVER **EXCEPT FOR SERVICING.**

BEFORE REMOVING ACCESS COVER YOU MUST:

- - LOCKOUT & TAGOUT DISCONNECT SWITCH
- - TURN CONTROL PANEL KEY SWITCH TO "OFF" POSITION
- - REMOVE KEY

CAUTION

GATE MUST BE CLOSED BEFORE OPERATING COMPACTOR

DO NOT OPERATE MACHINE **UNLESS CONTAINER IS** PROPERLY ATTACHED.

A CAUTION

OPERATORS — ALL PERSONS OPERATING THIS COMPACTOR ARE TO READ THE OPERATORS MANUAL AND UNDERSTAND THE SAFETY MESSAGES ON THIS MACHINE.

- 1. Keep compactor area clean and clear of obstructions.
- Inspect hydraulic hoses, fittings and electrical hook-up before cycling compactor. Do not use if repairs are needed.
- 3. Periodic inspection and maintenance is required, safety shields, access doors, and safety devices shall be functionally maintained. (See Manual)
- 4. DO NOT fill with heavy material, check with hauler for maximum capacity. Manual unloading may be required if overloaded.
- 5. Obey all warnings and safety instructions.
- 6. Obey all manufacturers operating instructions.

KEEP BYSTANDERS CLEAR

74-270

Escaping fluid under pressure can penetrate the skin causing serious injury. Avoid the hazard by relieving pressure before disconnecting hydraulic lines.
Tighten all connections before applying pressure. Search for leaks with a piece of

cardboard. Protect hands and body from high pressure fluids.

If an accident occurs, see a doctor immediately. Any fluid injected into the skin must be surgically removed thin a few hours or gangrene may result. INSPECT the hose assembly before each use.

REPLACE the hose assembly immediately it:

- ACE the hose assembly immedialely ii: The jacket of the hose appears abnormal. You have reason to believe it may be abnormal. There is any fluid leekage. The couplings are damaged. The hose is damaged or kinked.

- The reinforcement is visible through the jacket.

74-276





See page P33 in this Owner's Manual for proper location of decals.

9/96